

ID	Precinct	Project	From	To	Project Type	Description	Cost Estimate
RC2	4	Morton Road	FM 2855	Pitts Road	Capacity	Widen from 2 to 4 lane with median and sidewalks; intersection improvements	\$ 40,618,000.00
RC3	2	Joseph Road	Fields Store Road	Kickapoo Road	Capacity	Widen from 2 -lane to 3-lane with center-turn lane; intersection improvements	\$ 34,243,000.00
RC6	4	Schlipf Road	Morton Road	US 90	Capacity	New roadway to 4 lane with median	\$ 29,815,000.00
RC7	3&4	Clay Road	FM 2855	Waller County Line	Capacity	Widen from 2 to 4 lane with median and sidewalks; intersection improvements	\$ 34,951,000.00
RC8	4	Bartlett Road	Franz Road	Clay Road	Capacity	New roadway to 4 lane with median and sidewalks; intersection improvements	\$ 26,800,000.00
RC9	3	Stockdick Road	FM 2855	Schlipf Road	Capacity	Widen from 2 to 4 lane with median; intersection improvements	\$ 12,500,000.00
R10	1&3	Cochran Road	US 290 Business	Brumlow Road	Capacity	Widen from 2-lane to 3-lane with center-turn lane; intersection improvements	\$ 11,500,000.00
<b>Total Roadway Capacity</b>							<b>\$190,427,000.00</b>
RS1	1	Buller Intersection	Garrett Road	FM 1458	Capacity	Realign intersection to address crash safety concern.	\$ 9,374,000.00
RS2	2	Bowler at Kyle Road			Intersection Improvement	Additional signage and striping, curb radii improvements and lighting	\$ 500,000.00
RS8	3	Adams Flat Road	FM 359	Wilson Road	Maintenance	Mill and overlay existing 2 lane roadway (PCI - Poor - 53)	\$ 778,000.00
RS9	2&3	Old Houston Highway at Blinka Road			Intersection Improvement	Additional signage, striping, and realignment of curb radii.	\$ 42,000.00
RS10	2	Riley Road at Stonebridge Pkwy			Intersection Improvement	Additional signage, striping and lighting improvements.	\$ 21,000.00

ID	Precinct	Project	From	To	Project Type	Description	Cost Estimate
RS11	2	Hegar Road at Magnolia Road			Intersection Improvement	Install overhead flashing beacon, additional signage, striping, and pavement markings. Install rumble strips on westbound approach.	\$ 107,000.00
RS12	3	Wilson Road at FM 529/362			Intersection Improvement	Add LED flashing chevrons, relocate stop sign and signal cabinets, and install guardrail. If warranted, consider traffic signal.	\$ 21,000.00
RS13	3	Morrison Road at FM 529/2855			Intersection Improvement	Install overhead flashing beacon, additional signage, striping, and pavement markings. Widen shoulder on W leg of intersection or construct EB right-turn deceleration lane	\$ 192,000.00
RS14	1	Wyatt Chapel at FM 1488			Intersection Improvement	Deceleration lane along FM 1488, additional signage, and pavement markings.	\$ 155,000.00
RS15	3	Morrison Road	FM 362	Pattison Road	Maintenance	Mill and overlay existing 2 lane roadway (PCI - Very Poor - 28)	\$ 1,215,000.00
RS16	1	Cedar Creek Road	Double Culvert Road	SH 6	Maintenance	Mill and overlay existing 2 lane roadway (PCI - Serious - 20)	\$ 442,000.00
RS17	1	Double Culvert Road	FM 1736	Cedar Creek Road	Maintenance	Mill and overlay existing 2 lane roadway (PCI - Serious - 20)	\$ 1,518,000.00
RS18	1	Robichaux Road	Garrett Road	FM 1458	Maintenance	Mill and overlay existing 2 lane roadway (PCI - Poor - 54)	\$ 1,154,000.00
RS19	4	Neuman Road	FM 362	Depot Street	Maintenance	Mill and overlay existing 2 lane roadway (PCI - Poor - 34)	\$ 1,638,000.00
RS22	2	Mayer Road	FM 1488	FM 362	Maintenance	Mill and overlay existing 2 lane roadway (PCI - Very Poor - 39)	\$938,000.00
RS23	2&3	Penick and Mathis Road	Betka Road	Hebert Road	Maintenance	Mill and overlay existing 2 lane roadway (PCI - Very Poor to Serious)	\$2,625,000.00

ID	Precinct	Project	From	To	Project Type	Description	Cost Estimate
RS26	2	N Reids Prairie Road	Maverick Ln	Lake Road	Bridge Improvement	Approx 392 ft (Approx 292 ft from opening to closing and 50 ft of buffer on both sides) 5 columns	\$3,500,000.00
	2	Kyle Drive	N Reids Prairie Road	Royal Oak Drive	Bridge Improvement	Approx 397 ft (Approx 297 ft from opening to closing and 50 ft of buffer on both sides) 5 columns	
RS27	2	Riley Road	Kyle Drive	Walnut Ridge Drive	Bridge Improvement	Approx 357 ft (Approx 257 ft from opening to closing and 50 ft of buffer on both sides) 5 columns	\$3,500,000.00
	2	Riley Road	Walnut Ridge Drive	Riley Road	Bridge Improvement	Approx 370 ft (Approx 270 ft from opening to closing and 50 ft of buffer on both sides)	
<b>Total Roadway Safety/Maintenance</b>							<b>\$27,720,000.00</b>
Partnership projects include projects that cities or other governmental/public agencies and organizations may apply for on infrastructure improvements. Proposed projects must be in Waller County or provide a direct, immediate nexus to infrastructure in Waller County. Projects included in this category may have been included in another project document or planning nstudy such as a Comprehensive Plan or Master Plan.							
<b>Total Roadway Partnership Projects</b>							<b>\$40,000,000.00</b>